

Savaria Eclipse Home Elevator

Liftavator Inc

Standard Equipment

- Capacity: 950 lb
- 4 Stop
- Fully automatic operation
- Running speed: 40 ft/min
- Illuminated automatic push button operation on hall call stations; in-use indicator lights
- Digital display (floor and directional indicator) in car operating panel (COP)
- Available alpha numeric button marking
- Homing feature
- 80" cab height
- ¾" Unfinished stain grade hardwood veneer cab, anodized aluminum metal fixtures, stainless automatic bi-fold cab door, automatic recessed LED lighting
- Surface-mount telephone
- 36 month limited parts warranty, 24 month labor warranty